

DO NOT SCALE. IF IN DOUBT ASK!



25 x 25 x 0.7mm MIN THICK GALVANISED ANGLE CLAMPING THE BARRIER TO THE SUPPORTING ANGLE.

50 x 50 x 0.7mm MIN THICK GALVANISED ANGLE SUPPORTING THE INSTALLATION.



FIRE RATED FIXINGS AND PENNY WASHERS SECURING THE BARRIER TO THE CLAMPING ANGLE AT 600mm CENTRES.

FIRE RATED FIXINGS SECURING THE ANGLES AT 250mm CENTRES.

150mm OVERLAP FOLDED BACK TO PROTECT ANGLE.

2 BEADS OF FIREFLY™ HIGH TEMPERATURE ADHESIVE.

FIREFLY™ TITAN LITE™ BARRIER.



TITAN LITE™ IS A 3 LAYER SYSTEM AND MUST BE INSTALLED AS SUCH.

### TITAN LITE™ - TOP FIX

TBA PROTECTIVE TECHNOLOGIES LTD

ARTIST: JC

DRAWING NO:

UNIT 3, Transpennine Trading Estate, Gorrells Way  
Rochdale, OL11 2PX, United Kingdom

APPROVED: DA

**T - 002**

T: +44 (0)1706 758 817  
E: Technical@TBAFIREFLY.com  
W: www.tbafirefly.com

DATE: 07/12/2022

REVISION: 1

SCALE: NTS

IN SEQUENCE: 1/1

ALL RIGHTS RESERVED. NO PARTS OF THIS DRAWING MAY BE USED REPRODUCED, ALTERED, STORED IN A RETRIEVAL SYSTEM OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE PRIOR WRITTEN PERMISSION OF TBA PROTECTIVE TECHNOLOGIES LTD. WHILST EVERY EFFORT HAS BEEN MADE TO COMPLY WITH THE CURRENT STATUTORY REGULATIONS, IT IS THE USER'S RESPONSIBILITY TO ENSURE THAT THE FINAL DETAILING AND INSTALLATION MEETS THE REQUIREMENTS OF RELEVANT REGULATORY AUTHORITY (OFTEN BUILDING CONTROL). PLEASE CHECK [www.tbafirefly.com](http://www.tbafirefly.com) TO ENSURE THAT YOU ARE USING THE CORRECT AND CURRENT VERSION. COPYRIGHT 2022

