

DO NOT SCALE. IF IN DOUBT ASK!

MECHANICAL SUPPORT REQUIRED EVERY 8m MAXIMUM,  
BOTH HORIZONTALLY AND VERTICALLY.

TOP FIX.  
(T-002)

50 x 50 x 0.7mm MINIMUM THICK CONTINUOUS GALVANISED ANGLE.  
SUPPORTED WITH FIRE RATED FIXINGS AT THE TOP AND BOTTOM FIX.

A.

DETAIL A.

50 x 50 x 0.7 mm MINIMUM THICK CONTINUOUS GALVANISED ANGLE.  
FIXED TO THE VERTICAL ANGLE WITH FIRE RATED FIXINGS AS REQUIRED.

150mm MINIMUM OVERLAP FOLDED OVER TO COVER ANGLE.


50 x 50 x 0.7 mm MINIMUM THICK CONTINUOUS GALVANISED ANGLE.

FIRE RATED FIXINGS SECURING THE TWO HORIZONTAL ANGLES AT 250mm CENTRES.

FIRE RATED FIXINGS AND PENNY WASHERS SECURING THE BARRIER  
TO THE ANGLE AT 600mm CENTRES.

2 BEADS OF FIREFLY™ HIGH TEMPERATURE ADHESIVE.

BOTTOM FIX.  
(T-004)



FOR LARGER INSTALLATIONS CONSIDER OTHER DESIGN/LOADING CRITERIA (e.g: WIND).  
CONTACT THE MANUFACTURER FOR CLARIFICATION ON NON-STANDARD INSTALLATIONS.

TITAN LITE™ - EXTENDED DROP

TBA PROTECTIVE TECHNOLOGIES LTD

ARTIST: JC

DRAWING NO:

UNIT 3, Transpennine Trading Estate, Gorrells Way  
Rochdale, OL11 2PX, United Kingdom

APPROVED: DA

T - 017

T: +44 (0)1706 758 817  
E: Technical@TBAFIREFLY.com  
W: www.tbafirefly.com

DATE: 07/12/2022

REVISION: 1

SCALE: NTS

IN SEQUENCE: 1/1

ALL RIGHTS RESERVED. NO PARTS OF THIS DRAWING MAY BE USED REPRODUCED, ALTERED, STORED IN A RETRIEVAL SYSTEM OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE PRIOR WRITTEN PERMISSION OF TBA PROTECTIVE TECHNOLOGIES LTD. WHILST EVERY EFFORT HAS BEEN MADE TO COMPLY WITH THE CURRENT STATUTORY REGULATIONS, IT IS THE USER'S RESPONSIBILITY TO ENSURE THAT THE FINAL DETAILING AND INSTALLATION MEETS THE REQUIREMENTS OF RELEVANT REGULATORY AUTHORITY (OFTEN BUILDING CONTROL). PLEASE CHECK [www.tbafirefly.com](http://www.tbafirefly.com) TO ENSURE THAT YOU ARE USING THE CORRECT AND CURRENT VERSION. COPYRIGHT 2022

